



LENGTH	CY	WEIGHT
13'-0"	1.85	7,400
15'-0"	2.13	8,520
17'-0"	2.41	9,640
19'-0"	2.70	10,800
21'-0"	2.98	11,920

PRECAST OF MAINE
 139 MAIN STREET, P.O. BOX 307
 TOPSHAM, ME 04086
 207-729-1628, FAX: 207-729-8710

PROJECT: PRECAST THRESHOLDS

CUSTOMER: _____ ENGINEER: N/A

DATE: 12/13/11 DRAWN BY: MJB DRAWING NUMBER: 001

SCALE: NTS

- DESIGN NOTES:
1. CONCRETE TO BE 5,000 PSI @ 28 DAYS.
 2. REINFORCING TO BE GRADE 60, BLACK.